



QUOTATION CALL NOTICE

No. 1246 /ITIDKL Dt. 18-12-2020

Sealed Quotations are invited from the authorized Manufacturers/Dealers/ Distributors/Service provider, having valid GST for supply and installation of **Fire safety and prevention measures in Institute building of Govt. ITI, Dhenkanal** as per the specification and term & condition given below.

Interested firms/Supplier may submit their offers to the undersigned super scribing as "Quotation for **supply & Installation of Fire safety items**" on the sealed cover by **10.30AM of 4.1.2021**, which will be opened on same day at 11.00AM at Govt. ITI, Dhenkanal.

Term & Conditions

- 1- The rate quoted by the Bidder shall be fixed for the duration of the contact and shall not be subject to adjustment on any account.
- 2- The purchaser will evaluate and compare the quotations determined to be substantially responsive i.e. which are properly signed and conformed to the specifications.
- 3- The price shall be quoted in Indian rupee only.
- 4- All the materials enclosed as **Packages** shall be quoted strictly as per the Specification & suitability against each item in serial order with minimum 1 year Guarantee on each item.
- 5- The Quoted price shall be exclusive of all taxes with free delivery and installation charges to the consignee Institute. The GST to be shown distinctly & separately.
- 6- The supplier may pre-visit the Institute for proper assessment of installation locations.

The under signed has right to cancel/ reject or extend any or all quotations without assigning any reason thereof. A copy of this notice can be downloaded from the Institute website "www.govtidadkl.co.in".

Encl: List of materials: **Package A to E**


(Er. C.S. Tripathy)
Principal
Govt. ITI, Dhenkanal

Memo No. 1247(B) Dt. 18-12-2020

Copy to Notice Board of Institutes/ Collectorate, Dhenkanal/ RIC, Dhenkanal for information and necessary action.


Principal
Govt. ITI, Dhenkanal



Package-A

Name of the work:- Installation of Overhead Tank for Fire safety measure

Sl. No.	Name & Specification of the Materials	Make/ Brand	Rate per Quantity	GST
1	PVC Water tank, Capacity 2000 liters 2 layer with PVC pipe fitting from the existing water supply point to the water pump point including over flow system and necessary mason works in the roof of new Workshop building.	Sintex or equivalent	Each	
2	PVC Water tank, Capacity 2000 liters 2 layer with PVC pipe fitting from the existing water supply point to the water pump point including over flow system and necessary mason works in the roof of Administrative building.	Sintex or equivalent	Each	


 Principal 18/12/2020
 Govt. ITI, Dhenkanal


Package-B

Name of the work:- Installation of MS Pipe water supply connection for Fire safety measure in Administrative building

Sl. No.	Name & Specification of the Materials	Make/ Brand	Rate per Quantity	GST
1	50 mm MS pipe laying from overhead water tank of Administrative building to the Hose reel installation points including MS fittings and double enameled coated colouring in ground floor & first floor of building	Standard quality	Each Ft.	
2	Supply and Installation of 1.5Hp single phase Water Pump between storage Water tank and MS Pipe delivery system to extinguish fire including electric supply connection.	As per approved norm	Each	


 Principal 18/12/2020
 Govt. ITI, Dhenkanal


Package-C

Name of the work:- Supply and Installation of Hose Reel for Fire safety measure


Sl. No.	Name & Specification of the Materials	Make/ Brand	Rate per Quantity	GST
1	Supply and installation of Hose Reel of 30mtrs flexible pipe with drum, stand, pressure Nozzle, water Valves etc.	Standard Quality, ISI specification	Each	


Principal
Govt. ITI, Dhenkanal


Package-D

Name of the work:- Supply and Installation of Fire Extinguishers.

Sl. No.	Name & Specification of the Materials	Make/ Brand	Rate per Quantity	GST
1	Supply and installation of Fire extinguishers 6kg capacity ABC type	ISI specification	Each	
2	Supply and installation of Fire extinguishers 6kg capacity CO ² type	ISI specification	Each	


Principal
Govt. ITI, Dhenkanal


Name of the work:- Installation of MS Pipe water supply connection for Fire safety measure in New Workshop building

Sl. No.	Name & Specification of the Materials	Make/ Brand	Rate per Quantity	GST
1	50 mm MS pipe laying from overhead water tank of New Workshop building to the Hose reel installation points of New workshop building and IMC building including MS fittings and double enameled coated colouring.	ISI specification	Each Ft.	
2	Supply and Installation of 1.5Hp single phase Water Pump between storage Water tank and MS Pipe delivery system to extinguish fire including electric supply connection in New Workshop building roof.	As per approved norm	Each	

₹ 18112720

Principal
Govt. ITI, Dhenkanal

[Signature]